BANGALORE DIVISION.

Notification dated 10th December 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 6th January 1937 for constructing Administrative Block to the Veterinary Dispensary at Anekal. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred and twenty-five only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Administrative Block to the Veterinary Dispensary at Anekal" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9 Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Approximate quantities required for the construction of Administrative Block to the Veterinary Dispensary at Anekal.

Sl. No.	Items of work	Unit	Quantity	Rate sanctioned	Rate quoted in	
					Figures	Words
				Rs. a. p.		
1	Earthwork excavation for foundation and filling in basement ..	C.yd.	61⅓	0 2 6		
2	Burnt stone jelly concrete in lime mortar	C.ft.	552	0 3 6		
3	Size stone in clay for foundation and basement	,,	1,024	0 3 0		
4	Burnt brick in clay	,,	1,483	0 3 0		
5	Burnt stone slabs dressed and set in mortar 4″ to 6″ thick	S.ft.	204	0 4 0		
6	Burnt stone slabs dressed 6″ thick and fixed in mortar	,,	115	0 6 0		
7	Dressed stone pillars 9′ height and 8″ sqr. in section with pedestal and capital	Each	6	12 0 0		
8	Teakwood wrought and put up complete including wood oiling ..	C.ft.	60.60	5 0 0		
9	Rolled steel girders and joists fixed and painted	Cwt.	27.2	10 8 0		
10	Jack arched terrace roof (9″) thick ..	Sqr.	366	35 0 0		
11	Alternative for 9th and 10th items reinforced cement concrete roofing 6″ to 7″ thick	,,	366	50 0 0		
12	Roofing with 1st Class Mangalore Tiles on 2″×1″ T.W. Reepers ..	Sqr.	987	24 0 0		

Sl. No.	Items of work	Per	Quantity	Rate sanctioned	Rates to be quoted in	
					Words	Figures
13	Ridge tiles set in mortar and pointed with cement	R.ft.	85	0 7 0		
14	Parapet wall as per design	,,	56	1 0 0		
15	Burnt brick in mortar cornice 9″×9″ including plastering, white washing, etc., ...	,,	59 0	0 6 0		
16	Teakwood battened door with painting	S.ft.	140	1 4 0		
17	Do windows do	,,	108	1 8 0		
18	Do shelves including horizental planks with painting ..	,,	18	1 4 0		
19	Plastering with mortar $\frac{3}{4}$″ thick ..	Sqr.	3,223	3 0 0		
20	Flooring with $1\frac{1}{4}$″ to $1\frac{1}{2}$″ thick cuddapah slabs on 4″ thick concrete bed and cement pointing	Sqr.	7.38	25 0 0		
21	Alternative for item (20) flooring with 1″ cement concrete over 3″ stone jelly concrete in mortar and plastering with cement $\frac{1}{2}$″ thick mixed with red ochre and cut into squares, etc., complete	,,	7.38	20 0 0		

Notification dated 14th December 1936.

It is hereby notified for the information of the public that unserviceable stores will be sold by public auction on the 8th January 1937, at 9 A.M. in the premises of the Office of the Executive Engineer, Bangalore Division, Bangalore. The terms and conditions of the sale are:—

(*a*) The articles will be sold in lots and knocked down to the highest bidder. In the event of any dispute arising between two or more bidders offering the same price, the lot or lots shall be put up again and resold.

(*b*). All articles purchased shall be at the risk of the purchaser thereof from the time of sale.

(*c*) Cash shall be paid in full for lots purchased by bidders before delivery and the articles shall not be permitted to be removed from the place of auction until the sale is confirmed by the Executive Engineer.

(*b*) In case of default of payment of purchase money by any bidder, the articles shall be resold at the risk and cost of the bidder who shall also be liable to make good the Government losses arising thereby.

The following is the list of unserviceable articles available for sale:—

Survey and Mathematical Instruments.

Refill 100′ ..	1
Stop watch ..	1

Tools and Plant.

Buckets Galvzed. ..	17
Pans mortar ..	2
Tamper flat ..	1
$2\frac{1}{2}$″ brass locks ..	2
Iron locks ..	4
Mumties ..	13
Pick Axis ..	9
Sprit level ..	1
1″ steel bar of short lengths ..	10
Spanners of sizes ..	6
Boring set ..	1
Aluminium tumblers ..	9
Badges for peons brass ..	15
Poona cups ..	7
Files flat ..	3
Files half-round ..	4
Augers ..	2
Bombay Mumties ..	22
Sledge Hammers ..	2

Famine Reserve Tools.

Stone breaking hammers ..	5

Office furniture.

Lanterns Dietz ..	8
Rubber stamps ..	3
Do for Pass order ..	1
Do for obtaining payees' receipt ..	3
Enamel Tumblers ..	2

Surplus.

Trolley couplings ..	57
Do links ..	57
Do plates ..	29
Rails of short length from 2 to 3′ long	405R.ft.
G. I. Collars of sizes ..	24No.
C. I. Plug cocks ..	16
Fish plates ..	379
Palmirah brushes ..	7
Wire Brushes ..	13

Stock.

Creosoted fence posts ..	2
Empty cement bags ..	69

N. SUBBA RAO,
Executive Engineer.